TUMKUR DIVISION.

Abstract Notification dated 9th August 1936.

Attention of the public is drawn to Notification calling for tenders for the Restoration of Hatridurga Bettahally Tank in Kunigal Taluk in pages 1246-1247, Part VI in the *Mysore Gazette*, dated 13th August 1936. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M. on 10th September 1936.

An earnest money of Rs. 500 in cash should accompany the tender.

Notification dated 12th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 14th September 1936 for the maintenance work to Tumkur Amanikere Tank Register No. 1, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for maintenance work to Tumkur Amanikere Tank, Tumkur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for maintenance work of Tumkur Amanikere Register No. I of Tumkur Taluk.

Sl. No.	Items of work	Per	Rate	Quantity
			Rs. a. p.	
1	Earthwork with carting and consolidation (Bed earth to be taken including lift and lead)	C.yds.	0 4 0	10,962
2	Rooting out thick jungle from 31st to 39th Grades ..	Grades.	3 0 0	9
3	Removing Ant Hills and fixing with sand	No.	1 0 0	4
4	Cutting grips three lines (2'×1') 39 Grades (3×33×$\frac{2}{3}$×$\frac{1}{3}$) 22	C.yds.	0 2 6	858
5	Turfing front slope	S.yds.	0 1 0	2,360

Notification dated 15th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 14th September 1936, for Construction of a Dispensary Building at Amruthur, Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees (200) two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Construction of a Dispensary Building at Amruthur, Kunigal Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Mysore Teakwood should be used in all cases of wood work obtainable in Mysore, Shimoga and Tarikere Depots.

Abstract estimate for Constructing the Rural Dispensary at Amruthur, Kunigal Taluk.

Serial No.	Descripiton of work	Per	Rate	Quantity
			Rs. a p.	
1	Earthwork excavating foundation and filling in basement	C.yds.	0 4 0	46
2	Stone Jelly concrete in mortar	C.ft.	0 4 0	215
3	Burnt size stone or trap in mud filling foundation ..	,,	0 3 6	867
4	Burnt size stone in clay hammer dressed with bond stones	,,	0 3 9	599
5	Burnt brick in clay	,,	0 3 6	1,254
6	Brick in chunnam	,,	0 4 6	481
7	Teakwood doors pannelled with Silicate painting ..	S.ft.	2 4 0	213
8	Teakwood windows pannelled with $\frac{3}{4}$" Iron Bar and Silicate painting	,,	2 8 0	116
9	Burnt stone slabs 6" thick dressed and fixed ..	,,	0 6 0	361
10	Do 9" do ..	,,	0 9 0	15
11	Cut stone pillars with 7" square with base and capital	No.	15 0 0	8
12	Teakwood wrought and put up with wood oiling ..	C.ft.	6 0 0	82·14

Serial No.	Description of work	Per	Rate	Quantity
			Rs. a. p.	
13	Roofing with first class Mangalore tiles on teak reepers	Sqrs.	30 0 0	9·18
14	Ridge tiles set in mortar and cement pointing ..	R.ft.	0 8 0	97
15	Chunnam plastering	Sqrs.	3 8 0	34·87
16	Flooring with 1½″ cement concrete over 3″ stone jelly lime concrete and plastered over with red cement and cut to Mangalore flooring tiles pattern ..	,,	30 0 0	5·89
17	Cement pointing to basement	,,	3 0 0	3·12
18	Teakwood eave-boards 9″ plain all round the roof with painting	R.ft.	0 10 0	163
19	Chunnam border over roof	,,	0 5 0	87
20	Pucca Terrace	Sqrs.	40 0 0	1·58
21	Cornice 9″ thick	R.ft.	0 12 0	48
22	Valley plank one inch thick, 1½″ wide with zinc sheet 3 feet wide including mortar and cement border and cement pointing to tiles	S.ft.	2 0 0	80
23	Teakwood ½″ planked screen with painting including grove work and door-way at end	,,	1 4 0	56
24	Teakwood finials 2½ feet	No.	3 0 0	2
25	Teakwood pendants 1½ feet	,,	1 8 0	12
26	Chunnam mortar moulding in front as per elevation	L.S.	..	Rs. 5.
27	Providing rain water spouts	Each	1 0 0	4
28	Whitewashing, two coats	Sqrs.	0 4 0	35·47
	KITCHEN.			
1	Earthwork excavating foundation and filling in basement	C.yd.	0 4 0	7
2	Stone jelly concrete in mortar	C.ft.	0 4 0	50
3	Burnt stone or trap in mud	,,	0 3 6	116
4	Do Edges hammer dressed	,,	0 3 9	55
5	Burnt brick in mud	,,	0 3 6	230
6	Burnt brick in mortar	C.ft.	0 1 6	49
7	Burnt stone slabs 6″ thick roughly dressed ..	S.ft.	0 6 0	24
8	Teakwood battened door with silicate painting, etc., complete	,,	2 0 0	18
9	Teakwood windows with ¾″ iron bar, etc., complete with silicate painting	,,	2 0 0	5
10	Teakwood wrought and put up with wood oiling and tarring, etc., complete	C.ft.	6 0 0	7·54
11	Roofing with First Class Mangalore pattern tiles on teak reepers with oiling, etc., complete ..	Sqrs.	30 0 0	2·29
12	Ridge tiles set in mortar	R.ft.	0 8 0	15
13	Chunnam plastering	Sqrs.	3 8 0	5·29
14	Whitewashing with two coats	,,	0 4 0	5·29
15	Binding wall over roof	R.ft.	0 3 0	28
16	Flooring with Cuddappah slabs over 3″ concrete bed and cement pointing	Sqrs.	30 0 0	0·70
17	Cement pointing to basement	,,	3 0 0	0·45
18	Providing mortar and pestle	L.S.	..	Rs. 10
	LATRINE.			
1	Earthwork excavation	C.yd.	0 4 0	6
2	Burnt stone or trap in mud	C.ft.	0 3 6	151
3	Burnt brick in mud	,,	0 3 6	308
4	Burnt brick in mortar coping with chunnam plastering and whitewashing ,etc., complete	R.ft.	0 6 0	51
5	Whitewashing with two coats	Sqrs.	0 4 0	5·79
6	Chunnam plastering	,,	3 8 0	5·79
7	Flooring with Cuddappah slabs over 3″ concrete bed and cement pointing, etc., complete	,,	30 0 0	0·45
8	Providing cut stone seats	Each	2 8 0	6

N. G. KRISHNAIENGAR,
Executive Engineer.